

2100 19TH STREET
SACRAMENTO CA 95818
916.446.2466

PROJECT MANUAL

PARKWAY ELEMENTARY SCHOOL
PLAY STRUCTURES AND SITE REPAIR

4720 FOREST PARKWAY
SACRAMENTO, CA 95823

ACCESS ONLY PROJECT

DSA APP # 02-120106
DSA FILE # 34-53

SACRAMENTO CITY UNIFIED SCHOOL DISTRICT

REPLACEMENT OF PLAY STRUCTURES AND OVERALL SITE REPAIR.

APRIL 2022

DIVISION 2 EXISTING CONDITIONS

PAGE INTENTIONALLY LEFT BLANK.

SECTION 02 41 19 – SELECTIVE DEMOLITION

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of contract, including General and Supplementary conditions and other Division 1 Specification sections, apply to work of this section.

1.2 SUMMARY

A. Definition: "Demolition" includes cutting into or removing existing construction and conditions to provide for the installation of other work.

B. Section includes Selective Demolition as follows:

1. Removal of existing play structure and associated footings, play area curbs and footings, play area bark / fall protection, tree and root system, fencing, outdoor basketball pole, assembly, and footings, as indicated on drawings and as required to accommodate new construction.

2. Protection of existing trees, outdoor athletic equipment, existing underground utilities, French drain, landscaping, concrete walkways, signage, AC paving, fencing and gates, and adjacent buildings / improvements indicated to remain.

3. Removal of any additional above-grade improvements, noted on plans.

4. Removal of additional below-grade improvements, noted on plans.

5. Disconnect, remove, cap and identify utilities for later reconnection, if noted.

6. Removal of materials from site and dispose of legally.

7. Temporary partitions to allow adjacent building occupancy.

8. Salvage of designated elements for repair / reinstallation as indicated on drawings.

1.3 RELATED SECTIONS

A. Section 01 50 00 – Temporary Facilities and Controls.

B. Division 31 Sections.

C. Division 32 Sections.

1.4 EXISTING CONDITIONS

A. District makes no representations of conditions other than can be reasonably inferred from examination of the above and assumes no responsibility for actual conditions of items or structures to be demolished.

B. Occupational Safety and Health Administration (OSHA), U.S. Code of Federal Regulations (CFR) Title 29 Part 1926—Occupational Safety and Health Regulations for Construction.

C. 2019 California Building Code (CBC) with Amendments.

1.6 SUBMITTALS

A. General: Refer to Section 01 33 00 – Submittals.

B. Methodology:

1. Submit overall demolition and removal procedures and schedule, including but limited to:

a. Detailed sequence of selective demolition and removal work, with starting and ending dates for each activity.

b. Indication of how long utility services will be interrupted.

c. Coordination for shutoff, capping, and continuation of utility services, and accurately record locations of capped utilities.

d. Coordination of District's continuing occupancy of portions of existing building and of District's partial occupancy of completed Work.

2. Submit a detailed written program for each aspect of selective removal process, including a description of methods and materials used for protection of adjacent areas scheduled to remain.

3. Submit procedures and/or drawing that indicate measures proposed for environmental protection, dust control, and noise control measures, proposed locations, and proposed time frame for measures.

D. Informational Submittals – Pre-demolition Photographs: Before commencing demolition, file with District and Project Manager, photographs documenting existing conditions that later could be mistaken for damage caused by demolition operations.

E. Shop Drawings: Indicate areas for demolition, removal procedures and removal

Replace trees and shrubs outside building area disturbed by operations.

C. In accordance with generally accepted construction practices, the Contractor shall be solely and completely responsible for working conditions at the job site, including safety of all persons and property during performance of the work. This requirement shall apply continuously and shall not be limited to normal working hours.

D. Safety Precautions: Prevent damage to existing elements identified to remain or to be salvaged and prevent injury to the public and workmen engaged on site. Demolish roofs, walls and other building elements in such manner that demolished materials fall within foundation lines of building. Do not allow demolition debris to accumulate on site. Pull down hazardous work at end of each day; do not leave standing or hanging overnight, or over weekends.

E. Protect existing items which are not indicated to be altered.

1. Protect utilities designated to remain from damage.

2. Protect trees, plant growth, and features designated to remain as final landscaping as shown on drawings and provide maintenance (including watering) to ensure their survival. Cut roots only as necessary, and as acceptable to the Landscape Architect.

3. Protect bench marks from damage or displacement.

F. Trees: Carefully protect existing trees that are to remain. Provide temporary irrigation as necessary to maintain health of trees.

1.9 MATERIALS OWNERSHIP

A. Unless otherwise indicated, materials and debris resulting from cutting, moving, or removal becomes property of Contractor.

B. On-site storage or sale of Contractor’s materials and debris shall not be allowed.

1.10 PROJECT CONDITIONS

A. Protect adjacent work to remain, and items to be salvaged, from damage.

B. Existing Conditions:

1. Do not interfere with use of adjacent buildings. Maintain free and safe passage to and from.

2. Do not close or obstruct walkways or driveways except as otherwise indicated without authorization of authority having jurisdiction. Do not store or place materials in walkways, driveways, or other means of egress.

3. Conduct selective demolition operations with not less than interference to adjacent building areas, public or private roadways, and walkways.

4. Maintain a protected egress and access at all times.

C. Conduct operations so as not to interfere with adjacent roads, driveways, walks, buildings, corridors, means of access and egress, work areas, and other adjacent occupied and used facilities.

1. Do not close or obstruct streets, walks, or other adjacent occupied or used facilities without permission from Owner and authorities having jurisdiction. Provide alternate routes around closed or obstructed traffic ways if required by governing regulations.

D. When unanticipated mechanical, electrical, or structural elements that conflict with the intended function or design are encountered, investigate and measure the nature and extent of the conflict. Promptly submit a written report to the Architect.

E. Verify that utilities have been disconnected and capped.

F. Report existence of hazardous materials or unsafe conditions.

3.2 PREPARATION

A. Interfaces with Other Work: Coordinate extent of selective demolition work with limits of new work and existing work to remain, and with demolition and modification requirements shown on the Drawings.

B. Protection: Protect existing materials, appurtenances and equipment which are not to be demolished. Existing materials, appurtenances and equipment, building exterior and interior, and landscaping altered or damaged during demolition work shall be repaired or replaced by the to match existing undisturbed conditions at no additional cost.

C. Existing Plants, Trees, Shrubs, Grass: Verify that existing plant life and features designated to remain are tagged or identified. The Architect will mark the features, trees, and shrubs to remain within the construction area. Contractor shall not commence clearing and grubbing operations until authorized by the Owner and all protective measures are in place.

H. Provide and maintain temporary partitions to prevent spread of dust, odors and noise to permit continued building occupancy.

I. Maintain path of travel for debris removal dust free and clean at all times.

J. Cover and protect windows and walls that are adjacent to areas to be demolished.

K. Protect smoke alarms and fire sprinklers on adjacent buildings from dust intrusion.

L. Use covered debris bins to remove and materials indicated. Location of debris bins shall be approved by Project Manager.

M. Noise Abatement: Comply with noise abatement ordinances.

N. Maintain parking areas, driveways, exterior walkways, exit paths, and landscaping in a clean, undisturbed condition. Any debris caused by selective demolition work shall be removed each day.

3.3 UTILITY SERVICES

A. Utility Requirements:

1. Locate and identify existing utility, service and irrigation system components affected by work of this contract. Review existing record drawings, conduct site investigations, field verify, contact Underground Service Alert and other qualified cable/pipe/line locator services, and implement all other means necessary to define the location of underground systems.

2. Prior to interruption of utility services, notify affected public utility companies and obtain instruction for carrying out disconnection. Take precautionary measures deemed necessary by public utility companies. Do not start selective demolition work until utility disconnecting and sealing have been completed and verified in writing.

3. Mark location of disconnected systems. Identify and indicate stub-out locations on Project Record Documents.

4. Where utility services are required to be removed, relocated or abandoned, provide bypass connections to maintain continuity of service to other parts of the building before proceeding with selective demolition.

5. Disconnect, remove, and cap designated utility lines within demolition areas. Accurately mark locations of disconnected utilities. Identify utilities and indicate capping locations on Project Record Documents.

6. Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.

7. Do not interrupt existing utilities serving occupied or operating facilities, except when authorized in writing by Owner and authorities having

1. Minimize interference with adjacent and occupied building areas, materials and equipment, and as required to allow the school's continued use of the facilities.

2. Investigate and measure the nature and extent of unanticipated items that conflict with intended function or design. Submit written report with accurate detailed information to Project Manager. While awaiting instructions from Project Manager, rearrange selective demolition schedule as necessary to

3.8 CLEANING

A. Site needs to be kept clean at the end of every day; no accumulation of piles of demolished material may occur.

B. Debris and rubbish shall be removed and transported in a manner that prevents spillage on streets or adjacent areas. Local regulations regarding hauling and disposal shall apply.

C. Disposal of debris and rubbish shall be at a facility that complies with the Federal, State and local regulations.

D. All disposal fees shall be paid by the Contractor.

E. Upon completion of selective demolition, tools, materials, debris, and rubbish shall be removed. Site shall be left clean. Remove temporary work.

F. Clean excess material from surface of all remaining paved surfaces and utility structures.

G. Power wash all concrete surfaces to remove stains, dried mud, tire marks, and rust spots.

END OF SECTION 02 41 19.

PAGE INTENTIONALLY LEFT BLANK.

DIVISION 7 – THERMAL AND MOISTURE PROTECTION

07 92 00 – Joint Sealants

PAGE INTENTIONALLY LEFT BLANK.

1.6 QUALITY ASSURANCE

2.2 MATERIALS, GENERAL

A. VOC Content for Interior Applications: Provide sealants and sealant primers complying with the following VOC content limits per 40 CFR 59, Subpart D (EPA Method 24):

2.4 SOLVENT-RELEASE-CURING JOINT SEALANTS

A. Butyl-Rubber-Based Joint Sealant: ASTM C1311. Manufacturer's standard one-part, nonsag, solvent-release-curing, polymerized butyl sealant and formulated with minimum of 75 percent solids to be nonstaining, paintable, and have a tack-free time of 24 hours or less.

1. Volatile Organic Compound (VOC) Content: 250 g/L maximum.

2. Color: As selected by Architect from manufacturer's standard colors.

B. Uses: Exterior and Interior use for sealing joints in concealed joints within metal assemblies, such as curtainwall joints, metal panel joining, bedding thresholds, secondary glazing seals, and areas where a seal is required against neoprene or EPDM gaskets.

C. Available Products and Manufacturers: Subject to compliance with requirements, solvent-release-curing joint sealants which may be incorporated in the work include, but are not limited to, the following:

1. BC-158, by Pecora Corporation.
2. Tremco Butyl Sealant, by Tremco Inc.

2.5 JOINT SEALANT ACCESSORIES

A. Cylindrical Sealant Backing: ASTM C1330, Type B non-absorbent, bi-cellular material with surface skin, or Type O open-cell polyurethane, as recommended by sealant manufacturer for application.

B. Bond Breaker Tape: Polymer tape compatible with joint sealant and adjacent materials and recommended by sealant manufacturer.

C. Joint Substrate Primers: Substrate primer recommended by sealant manufacturer for application.

D. Cleaners: Chemical cleaners acceptable to joint sealant manufacturer.

E. Masking Tape: Non-staining, non-absorbent tape product compatible with joint sealants and adjacent joint surfaces.

–

3.1 EXAMINATION

A. Examine joint profiles and surfaces to determine if work is ready to receive joint sealants. Verify joint dimensions are adequate for development of sealant movement capability. Verify joint surfaces are clean, dry, and adequately cured. Proceed with joint sealant work once conditions meet sealant manufacturer's written recommendations.

3.2 PREPARATION

A. Joint Surface Cleaning: Clean joints prior to installing joint sealants using materials and methods recommended by sealant manufacturer. Comply with ASTM C1193.

1. Remove curing compounds, laitance, form-release agents, dust, and other contaminants.

2. Clean nonporous and porous surfaces utilizing chemical cleaners acceptable to sealant manufacturer.

3. Protect elements surrounding the Work of this section from damage or disfiguration. Apply masking tape to adjacent surfaces when required to prevent damage to finishes from sealant installation.

3.3 SEALANT APPLICATION

A. Sealant and Primer Installation Standard: Comply with ASTM C1193 and manufacturer's written instructions applicable to products and applications indicated, except where more stringent requirements apply.

B. Joint Backing: Select joint backing materials recommended by sealant manufacturer as compatible with sealant and adjacent materials. Install backing material at depth required to produce profile of joint sealant allowing optimal sealant movement, per manufacturer’s recommendations and requirements.

C. Masking: Mask adjacent surfaces to prevent staining or damage by contact with sealant or primer. Remove tape immediately after tooling without disturbing joint seal.

D. Joint Priming: Prime joint substrates when recommended by sealant manufacturer or when indicated by preconstruction testing or experience. Apply recommended primer using sealant manufacturer's recommended application techniques. Confine primers to areas of joint sealer bond, do not allow spillage or migration onto adjoining surfaces.

E. Liquid Sealant Application: Install sealants using methods recommended by sealant manufacturer, in depths recommended for application. Apply in continuous operation from bottom to top of joint vertically and horizontally in a single direction. Apply using adequate pressure to fill and seal joint width.

1. Tool sealants immediately with appropriately shaped tool to force sealants against joint backing and joint substrates, eliminating voids and ensuring full contact.

2. Install sealant free of air pockets, foreign embedded matter, ridges, and sags.

3. Tool exposed joint surface concave using tooling agents approved by sealant manufacturer for application.

F. Cleaning: Remove excess sealant using materials and methods approved by sealant manufacturer that will not damage joint substrate materials. Remove masking tape

immediately after tooling joint without disturbing seal. Remove excess sealant from surfaces while still uncured.

3.4 PROTECTION

A. Protect joint sealers during and after curing period from contact with contaminating substances or from damage resulting from construction operations or other causes so that they are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out and remove damaged or deteriorated joint sealers immediately and reseal joints with new materials to produce joint sealer installations with repaired areas indistinguishable from original work.

3.5 FIELD QUALITY CONTROL

A. Remove sealants failing adhesion test, clean substrates, reapply sealants, and re-test. Test adjacent sealants to failed sealants.

3.6 EXTERIOR JOINT-SEALANT SCHEDULE

DIVISION 8 – DOORS AND WINDOWS

08 71 00 – Door Hardware

PAGE INTENTIONALLY LEFT BLANK.

PAGE INTENTIONALLY LEFT BLANK.

and packaging, with labels clearly identifying product name and manufacturer.

B. Storage: Store materials in clean, dry area indoors in accordance with manufacturer's instructions. Keep temporary protective coverings in place.

C. Handling: Protect materials and finish from damage during handling and installation.

1.9 WARRANTY

A. Provide minimum one (1) year warranty against defects in materials and workmanship, unless otherwise specified.

PART 2 – PRODUCTS

2.1 MANUFACTURER

A. Available Manufacturers: Subject to compliance with requirements, products which may be incorporated in the work include, but are not limited to, the following:

1. Basis of Design: Porter Athletic, Inc.,

B. Outdoor Basketball Backboards: Basis of Design, Porter Athletic, Model No. 234-3 fan-shaped, cast-aluminum backboard.

1. Provide each outdoor backstop with backboard.

2. Backboard: Official size, 54 inches by 39 inches, and shape. Orange perimeter and target-area markings.

3. Material: Cast-in-permanent-mold process from high-tensile, No. 319 aluminum. Cast with structural reinforcing ribs on backside with heavy, 1-1/2-inch deep perimeter flange to provide maximum rigidity.

4. Backside of Backboard: 8 tapped holes, 3/8-16, to fit normal mounting attachments without exposed bolt heads on front face of unit.

5. Backboard Drilling: For front-mount goal, 5-inch by 5-inch hole pattern. Compatible with direct-mount support structures.

6. Goal Mounting Holes: 4, molded with integral, hex-shaped cavity located on front side of backboard to independently mount backboard to rear-support structure Center-Strut to provide option of removing goal for seasonal use or to prevent vandalism or unauthorized use.

7. Finish: White powder coated.

C. Outdoor Basketball Goals: Basis of Design, Porter Athletic Inc. Model No. 235 high-strength Super Goal.

1. Provide each outdoor backstop with goal.

2. Rim: Fabricated from 5/8-inch diameter, high-strength, cold-drawn alloy steel, round-formed to 18-inch inside diameter ring.

3. Inside of Ring: Positioned 6 inches from face of backboard by heavy, L-shaped, formed- steel mounting plate with 5-inch by 4-inch and 5-inch by 4-1/2-inch mounting-hole centers for front mounting.

4. Brace Rim: Rigidly braced by 5/8-inch diameter, high-strength, cold-drawn alloy steel, round-formed and welded in position for maximum support.

5. Net Attachment Clips: 12 no-tie net attachment clips.

6. Net: White nylon net or Chain net, as specified by Architect.

7. Mounting Hardware: Plated.

8. Finish: Official orange powder coated.

2.3 EXISTING OUTDOOR ATHLETIC EQUIPMENT

A. Yellow Caution Band: Repaint on existing athletic equipment poles, from 2'-0" AFF to 5'-0" AFF, or as noted by the District.

PART 3 – EXECUTION

3.1 EXAMINATION

A. Examine areas and supporting structure to receive play field equipment. Notify Owner and Architect in writing of conditions that would adversely affect installation or subsequent use. Do not proceed with installation until unsatisfactory conditions are corrected.

3.2 INSTALLATION

A. Install play field equipment in accordance with manufacturer's instructions at locations indicated on the Drawings.

B. Install equipment plumb, level, straight, square, accurately aligned, correctly located, to proper elevation, and secure.

C. Install equipment using manufacturer's supplied hardware and fasteners.

D. Repair minor damages to finish in accordance with manufacturer's instructions and as approved by Architect.

E. Remove and replace damaged components that cannot be successfully repaired, as determined by Architect.

3.3 ADJUSTING

A. Adjust basketball backstops, backboards, and goals for plumb and level.

B. Adjust operating equipment to function properly and for smooth operation without binding.

3.4 CLEANING

A. Clean play field equipment promptly after installation in accordance with manufacturer's instructions.

B. Remove labels and temporary protective coverings.

C. Do not use harsh cleaning materials or methods that would damage finish.

3.5 PROTECTION

A. Protect installed play field equipment to ensure equipment will be without damage or deterioration at time of substantial completion.

END OF SECTION 11 66 00.

DIVISION 31 EARTHWORK

PAGE INTENTIONALLY LEFT BLANK.

PAGE INTENTIONALLY LEFT BLANK.

SECTION 32 12 00 – ASPHALT CONCRETE PAVEMENT

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division 01 Specification sections, apply to work of this section.

1.2 SCOPE

A. Verification and acceptance of established grades.

B. Weed killer.

C. Asphaltic concrete – aggregate base, prime coat, asphaltic concrete surface, crack fill, seal coat, and AC overlay.

1.3 RELATED WORK DESCRIBED ELSEWHERE

A. Section 02 41 19 – Selective Demolition.

B. Section 31 10 00 – Site Clearing.

C. Section 31 20 00 – Earthwork.

D. Section 32 13 00 – Cast-in-Place Site Concrete.

E. Section 32 17 00 – Paving Specialties.

1.4 APPLICABLE PUBLICATIONS

A. The following publications of the issues listed below, but referred to hereinafter by basic designation only, form a part of this specification to the extent required by the references thereto:

1. State of California, Department of Transportation, Standard Specifications for Road Construction, current edition.

2. ASTM International (ASTM):

a. ASTM D1557 – Test for Moisture-Density Relations of Soils Using 10-lb. Rammer and 18-inch Drop (Method D).

b. ASTM D2922 – Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth).

c. ASTM D3017 – Moisture Content of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth).

3. Sacramento County Department of Public Works (County Standards) Improvement Standards and Specifications.

4. "The Asphalt Institute" Specification Series No. 1 (SS-1, latest edition).

5. 2019 California Building Code (CBC), with Amendments.

1.5 STATE STANDARD SPECIFICATIONS

A. Whenever this specification is referenced, the following is understood:

1. Whenever the term "Engineer" occurs, it shall mean the Civil Engineer of this project.

2. Whenever a discrepancy occurs between the Standard Specifications and this specification, it is understood that this specification governs.

compaction and trueness to line and grade.

1.8 REQUIREMENTS

A. The aggregate base, tack coat, and bituminous course or overlay shall conform to the requirements of the Standard Specifications for Road Construction, State of California, Department of Transportation, latest edition.

1.9 SITE CONDITIONS

A. Environmental Requirements:

1. Base Course: Do not lay base course on muddy subgrade, during wet weather, or when atmospheric temperature is below 40°F.

2. Asphalt Surfacing: Do not apply asphaltic surfacing on wet base, during wet weather, or when atmospheric temperature is below 50°F.

B. Grade Control: Establish and maintain required lines and elevations.

1.10 DELIVERY, STORAGE AND HANDLING

A. Transport, store and handle in strict accord with the local jurisdiction.

B. Make delivery to job when notified by Contractor verifying that the job is ready to receive the work of this Section and that arrangements have been made to properly store, handle and protect such materials and work.

1.11 EXISTING SITE CONDITIONS

A. Contractor shall acquaint himself with all site conditions. If unknown active utilities are encountered during work, notify Architect promptly for instructions. Failure to notify will make Contractor liable for damage to these utilities arising from Contractor's operations subsequent to discovery of such unknown active utilities.

1.12 PROTECTION

A. Adequate protection measures shall be provided to protect workmen and passers-by on and off the site. Adjacent property shall be fully protected throughout the operations. Blasting will not be permitted. Prevent damage to adjoining improvements and properties both above and below grade. Restore such improvements to original condition should damage occur. Replace trees and shrubs outside building area disturbed by operations.

B. In accordance with generally accepted construction practices, the Contractor shall be solely and completely responsible for working conditions at the job site, including safety of all persons and property during performance of the work. This requirement shall apply continuously and shall not be limited to normal working hours.

C. Any construction review of the Contractor's performance conducted by the owner’s representative is not intended to include review of the adequacy of the Contractor's safety measures, in, on, or near the construction site.

3.5 CRACK FILLING

A. Existing pavement preparation and crack filling procedures shall conform to Section 37 of the Standard Specifications.

3.6 SLURRY SEAL

A. Slurry seal shall be Type I and shall conform to Section 37-3 of the Standard Specifications.

3.7 AC OVERLAY

A. Existing asphalt grinding, surface preparation, crack treatment, tack coat, and asphalt pavement overlay shall be performed in accordance with Section 39-2 of the Standard Specifications.

3.8 SAWCUTTING OF ASPHALT PAVEMENT

A. Use saw capable of cutting a minimum of 1-1/2 inches in depth. Mark cut line precisely with chalkline. Saw along line to provide a neat, uniform straight cut. Recut at Contractor's expense all edges that become broken or damaged.

3.9 ASPHALT CONCRETE

A. All materials shall be furnished by the Contractor. The bituminous concrete shall consist of mineral aggregate, uniformly mixed with bituminous material in a central plant in accordance with Section 39 of the Standard Specifications. The mixing plant and construction equipment shall conform to the requirements of Section 39.

B. Placing: Bituminous mixtures shall be delivered to the roadbed at temperatures

verifying weight, proportions, and character of materials and checking temperatures being maintained in the preparation of the mixtures.

3.11 TESTING

A. Compaction density testing shall be measured in accordance with ASTM D2922 and D3017 and shall be taken at locations selected by the Engineer.

B. Flood Tests: In the presence of the Construction Manager and prior to acceptance of the Work, paving surface shall be flooded to check for standing water. Water flood tests shall be accomplished with a water tank truck or with rain water. All depressions where water ponds shall not exceed a depth of more than 1 /16-inch fill. Any area that is not within the specified tolerance shall be brought to grade by removing the paving material in the area to be repaired. A minimum laying depth of 1.0 inch of the new pavement material at the joint line shall be provided. Repairs shall not be made to the pavement surface by feather edging at the joints.

END OF SECTION.

PAGE INTENTIONALLY LEFT BLANK.

D. Section 32 31 19 – Ornamental Metal Fencing and Gates.

E. Section 33 40 00 – Storm Drainage.

1.4 SUBMITTALS

A. Shop Drawings: Submit shop drawings for reinforcing steel, prepared in accordance with ACI 315. Indicate bending diagrams, assembly diagrams, splicing and laps of rods, and shapes, dimensions and details of bar reinforcing and accessories. Do not use scaled dimensions from structural drawings to determine lengths of reinforcing rods.

B. Contractor Mix Design: Submit a mix design for each type of concrete, including a complete list of materials including admixtures and the applicable reference specifications, and copies of test reports showing that the mix has been successfully used to produce concrete with the properties specified.

C. Certification: Submit one copy of the delivery ticket for each load of ready-mixed concrete, showing all information required by ASTM C94.

D. Pre-molded joint filler: Submit product data sheets showing properties and applicable specifications.

1.5 DELIVERY AND STORAGE

A. Do not deliver concrete until forms, reinforcement, and embedded items are in place and ready for concrete to be placed.

B. Store reinforcement in a manner that will avoid excessive rusting or coating with grease, oil, dirt, and other objectionable materials. Store in separate piles or racks so as to avoid confusion or loss of identification after bundles are broken.

PART 2 – MATERIALS AND PRODUCTS

2.1 CONCRETE

A. Contractor Furnished Mix Design: Design concrete mix in accordance with ACI 211.1. Slump shall be between 2 inches and 4 inches. The concrete shall have a 28-day compressive strength of 4,000 pounds per square inch.

2.2 OTHER MATERIALS

A. Cement: ASTM C150, Type I or II for all concrete. All cement for exposed concrete surfaces shall be of the same manufacture.

B. Water: Water, including free moisture and water in the aggregates, shall be fresh, clean, and potable.

C. Aggregates: ASTM C33, size No. 67 except as modified herein. Obtain all aggregates for exposed concrete surfaces from one source. Aggregates shall be free from any substance which may be deleteriously reactive with the alkalies in the cement.

D. Materials for Forms: Wood, plywood, steel, or other suitable material. Wood forms, for surfaces exposed to view in the finished structure, shall be boards or plywood. Dress boards to a uniform thickness, evenly match, and provide boards free from loose knots, holes, and other defects. Plywood shall be B-B concrete form panels conforming to PS-1. Surfaces of steel forms shall be free from irregularities, dents, and sags.

E. Reinforcing Bars: ASTM A615, Grade 60. All bars shall be deformed.

F. Materials for Curing Concrete: One of these options

1. Impervious Sheeting: Waterproof paper, polyethylene sheeting, or polyethylene coated burlap conforming to ASTM C171.

2. Liquid Membrane-forming Compound: ASTM C309, white-pigmented, Type 2, free of paraffin or petroleum.

G. Preformed Joint Filler: ASTM D1751, thickness as per plans.

PART 3 – EXECUTION

3.1 FORMS

A. General: Provide forms for all concrete at grade or above grade. Set forms true to line and grade and maintain so as to insure completed work within the allowable tolerances specified, and make mortar-tight. Construct forms so that they can be removed without damaging the concrete. Chamfer all exposed joints, edges, and external corners of concrete 3/4 inch unless otherwise indicated.

B. Coating: Before placing the concrete, coat the contact surfaces of forms with a nonstaining mineral oil, non-staining form coating compound, or two coats of nitrocellulose lacquer. Do not use mineral oil on forms for surfaces which are to be painted.

C. Tolerances and Variations: Set and maintain concrete forms to ensure that after removal of the forms no portion of the concrete work will exceed any of the tolerances specified in ACI 347.

3.2 PLACING REINFORCEMENT AND MISCELLANEOUS MATERIALS

A. General: Provide all bars, and other reinforcing materials as indicated or specified, together with all necessary wire ties, supports, and other devices necessary to install and secure the reinforcement properly. All reinforcement, when placed, shall be free from rust, scale, oil, grease, clay, and other coating, and foreign substances that would reduce or destroy the bond. Rusting of reinforcement shall not be a basis of rejection, provided that the rusting has not reduced the effective cross sectional area of the reinforcement, and provided that loose rust shall be removed prior to placing. Where cover over reinforcing steel is not indicated, it shall be in accordance with ACI 318.

B. Placing: Place reinforcement accurately as shown on the plans, or at the center of the slab, if not specified otherwise. Secure in place on suitable chairs, spacers, or

DIVISION 33 – **UTILITIES**

33 40 00 – Storm Drainage

PAGE INTENTIONALLY LEFT BLANK.