



Business Services  
Contracts Office  
5735 47th Avenue Sacramento, CA 95824  
(916) 643-2464

---

## **ADDENDUM NO. 2**

Date: May 3, 2018

Issued by: Sacramento City Unified School District

**Project: O.W. Erlewine Elementary School Roof & Asphalt Replacement**

You are hereby notified of the following changes, clarifications, or modifications to the original Contract Documents, Specifications, and Drawings. This Addendum shall supersede the original project documents, and shall take precedence over anything to the contrary therein. All Addenda shall be acknowledged in the Bid Form. Failure to do so may result in disqualification of the bid. All other conditions remain unchanged.

---

### I. RESPONSES TO QUESTIONS FROM BIDDERS:

1. Page A1.0 note 3 calls for demolishing existing roof pipe support for conduit, duct, and piping. Temporary support is also required. Permanent supports for piping and conduit are not addressed. Please confirm that details 1,2, and 3 A8.0 are to be installed as permanent supports. Please clarify spacing. Response: Details are to be installed as permanent supports. Conduit and Gas line support – Match existing or provide within 18" of all changes in direction and at 20' O.C maximum, whichever spacing is more stringent for the current condition.
2. Page A2.1, note 9, calls for detail 2/A8.0 for "roof equipment typ." What is meant by "roof equipment"? Notes points to ductwork. If it applies only to ductwork, at what spacing are the supports required? Response: The note should read "(N) curb for existing duct support." Match existing spacing for ductwork support.
3. At the pre-bid job walk a core sample was taken of the existing roof system. In the area that was cored the roofing was solid mopped to the deck and took part of the decking with the core. What are our options if the roofing can not be removed without damaging the decking? Response: District will field verify conditions during tearoff. There is an allowance for unforeseen roofing conditions.
4. Will we be required to remove and replace all the sheet metal mechanical curbs on the metal roofs? Response: Curbs will stay in place. Sheet metal over mechanical curbs on the metal roofs will be removed and replaced.



## II. PRICE PROPOSAL FORM

1. A price proposal form that includes a \$25,000 allowance for dry rot and a 10% Owner's Contingency is attached as Exhibit D to the RFP. Please include with the proposal form a detailed breakdown of all costs.

**END OF ADDENDUM NO. 1**

Attachment