



### **ADDENDUM NO. 1**

Date: January 19, 2021

Issued by: Sacramento City Unified School District

**Project: RFP 21-02, Cabling Infrastructure for E-Rate Year 24**

You are hereby notified of the following changes, clarifications, or modifications to the original Contract Documents, Specifications, and Drawings. This Addendum shall supersede the original project documents, and shall take precedence over anything to the contrary therein. All Addenda shall be acknowledged in the Bid Form. Failure to do so may result in disqualification of the bid. All other conditions remain unchanged.

---

#### 1. DRAWINGS

- a. Site maps have been added to the contract documents. Please see



Site	Cabling Needs	Notes
Mark Hopkins	Cabling Rooms 13-28 - 3 IDFs - SM Fiber	Using Map – “Mark Hopkins Proposed Upgrade.pdf” as the guide *Typical classroom layout 2 CAT6 Drops per wall, 2-CAT6A WAP drops, 1 phone, one clock/speaker, one teacher workstation (Phone/Teacher Workstation can be included in the 2 drops per wall) *IDFs - 3'
Earl Warren	Cabling to Room A4 - New IDF Cabling to Room 22-24 - New IDF Room 22	*4 Rooms Total - Typical classroom layout 2 CAT6 Drops per wall, 2-CAT6A WAP drops, 1 phone, one clock/speaker, one teacher workstation (Phone/Teacher Workstation can be included in the 2 drops per wall) Replace AP's cabling in these room with Cat6A *Room A4 - Cat6A from MDF, 2' Cabinet, (12 port Switch supplied by district), *Room 22 - Cat6A from IDF 4 Room 18, New IDF in Room 22 with 2' Cabinet, 48 port switch, pull back cable from Room 22-24 to Room 22
Luther Burbank	Cabling, Conduit/Trenching to J10 - New IDF	*Typical classroom layout 2 CAT6 Drops per wall, 2-CAT6A WAP drops, 1 phone, one clock/speaker, one teacher workstation (Phone/Teacher Workstation can be included in the 2 drops per wall) *Room J10 - 6 Strand SM home ran to MDF, x2-2" conduit, trench, asphalt, 2 AP external, 2' Cabinet, (12 port switch supplied by district)
Mark Twain	Cabling to Room 26	*1 Room Total - Add cabling to Room 26 from IDF in Room 22 *Typical classroom layout 2 CAT6 Drops per wall, 2-CAT6A WAP drops, 1 phone, one clock/speaker, one teacher workstation (Phone/Teacher Workstation can be included in the 2 drops per wall)
Oak Ridge	MM to SM Fiber	*Complete exchange from failing MM to SM fiber for this site (multiple strands have failed)
Sutterville	Cabling to Room 24 - New IDF	*1 Room Total - Typical classroom layout 2 CAT6 Drops per wall, 2-CAT6A WAP drops, 1 phone, one clock/speaker, one teacher workstation (Phone/Teacher Workstation can be included in the 2 drops per wall) *Cat6A from IDF Room 22 to Room 24, 2' cabinet with 12 port district supplied switch
Sequoia	Cabling to Rooms 29-30 - New IDF Room 29	*2 Room Total - Typical classroom layout 2 CAT6 Drops per wall, 2-CAT6A WAP drops, 1 phone, one clock/speaker, one teacher workstation (Phone/Teacher Workstation can be included in the 2 drops per wall) *Cat6A from IDF Room 24 to Room 29, 2' cabinet with 24 port district switch
John Cabrillo	Cabling to Rooms 26-27 - New IDF Room 26	*2 Room Total - Typical classroom layout 2 CAT6 Drops per wall, 2-CAT6A WAP drops, 1 phone, one clock/speaker, one teacher workstation (Phone/Teacher Workstation can be included in the 2 drops per wall) *SM Fiber from MDF to Room 26, 2' cabinet with 24 port district switch

